AL NAMARIQ BUILDING MATERIAL TRADING C

Certified Knauf Dry Construction Systems Distributor

P.O. Box 25569, Industrial Area, Sharjah, UAE • Tel: +971 6 5328033 • Fax: +971 6 5328302

Email: sales@alnamariq.ae • Certified Knauf BoQ Engineering Platform

COMMERCIAL QUOTATION

Ref: ANM-2026-459

Date: 11/09/2026

Project Name:	**Commercial Office Fitout & Partitions**	**Quotation No:**	**ANM-2026-459**
Client / Contractor:	**Main Contracting LLC**	**Project Scale:**	**1,000 M²**
Product Specified:	**KW111 - KNAUF SYSTEM KW 111**	**Sales Engineer:**	**Ram Prasad**

#	MATERIAL DESCRIPTION & SPECIFICATION	REQ / M²	UNIT	TOTAL QTY	RATE (AED)	TOTAL (AED)
A. KNAUF STANDARD SYSTEM COMPONENTS (11 ITEMS)						
1	**KNAUF Regular Gypsum Board GW-R 12.7x1220x2400mm**	2.050	m²	**2,050.00**	9.500	**19,475.00**
2	**KNAUF CW 70/35/0.6mm 3000mm**	2.000	m	**2,000.00**	4.200	**8,400.00**
3	**KNAUF UW 70/32/0.6mm 3000mm**	0.800	m	**800.00**	3.800	**3,040.00**
4	**KNAUF Insulation 50mm 16 kg/m3**	1.000	m²	**1,000.00**	6.500	**6,500.00**
5	**KNAUF Drywall Screw TN 3.5x25 Screw (1000)**	30.000	pcs	**30,000.00**	0.017	**510.00**
6	**KNAUF Hammer Fixing 6x40mm (200)**	1.600	pcs	**1,600.00**	0.120	**192.00**
7	**KNAUF Acoustical Sealing Tape 70mmx25m**	0.800	m	**800.00**	1.100	**880.00**
8	**KNAUF Acoustic Sealant 280ml**	0.200	pcs	**200.00**	12.500	**2,500.00**
9	**KNAUF Joint Tape 50mm/90m**	3.000	m	**3,000.00**	0.120	**360.00**
10	**KNAUF Readyfix Joint Compound 28Kg.**	0.800	kg	**800.00**	1.430	**1,144.00**
11	**KNAUF Wafer Head Screw LN 4.2x11mm (1000)**	2.000	pcs	**2,000.00**	1.028	**2,056.00**
	SUBTOTAL BASE SYSTEM ASSEMBLY:			**Rate: AED 45.06 / M²**		**AED 45,057.00**
B. KNAUF HEAD DEFLECTION MOVEMENT JOINTS (5 ITEMS)						
12	**KNAUF (FR) GW-TX 12.7x1200x2400mm (board strip)**	0.200	m²	**200.00**	13.500	**2,700.00**
13	**KNAUF Section Angle 60/25 0.5 x 3000mm**	0.700	m	**700.00**	2.200	**1,540.00**
14	**KNAUF FR Sealant 280ml**	0.150	pcs	**150.00**	16.000	**2,400.00**
15	**KNAUF Wedge Anchor (200)**	0.800	pcs	**800.00**	0.430	**344.00**
16	**KNAUF Concrete Screwbolt 7.5x100mm (100pcs)**	0.600	pcs	**600.00**	0.850	**510.00**
	SUBTOTAL HEAD DEFLECTION MOVEMENT JOINTS:			**Rate: AED 7.49 / M²**		**AED 7,494.00**
TOTAL COMMERCIAL OFFER VALUE (EXCL. VAT):						**AED 52,551.00**
FINAL EFFECTIVE RATE PER M² (ALL-INCLUSIVE):						**AED 52.55 / M² Standard Project Scale**

OFFICIAL COMMERCIAL TERMS & CONDITIONS:

1. Above consumption is based on theoretical calculation. The material requirement is based on the standard Knauf system
2. Material will be supplied as per bundle/packaging multiple in full trailer load only.
3. Non standard materials leadtime is approx 3-4 weeks upon receipt of confirmed order.
4. Merchandise or imported goods will take 6-8 weeks.
5. Delivery schedule is a must to plan supply and initiate production.
6. The technical proposal for this project will be submitted upon confirmation.
7. Standard sales terms & conditions apply.

PREPARED BY:

Ram Prasad
Al Namariq Estimating Dept.

AUTHORIZED BY:

Commercial Directorate
Al Namariq Sharjah Branch

CUSTOMER ACCEPTANCE:

Authorized Signatory & Stamp
Date: ____ / ____ / 2026